


ZIPP™ System

40 Stages Completed with 2 BHAs



HIGHLIGHTS

- Single Trip Perf-and-Frac
- Accurate Frac Placement
- No Additional Clean Out Run
- Durable Design

DETAILS

Location	Canadian County, Oklahoma
Formation	Woodford
Well Orientation	Horizontal
Conveyance	2" Coiled Tubing
Casing Size	5 1/2" 20#
Operation Depth	17,685 Ft
Number of Stages	40
Tools Used	ZIPP™ System

RESULTS

The customer planned to perforate 40 stages in a horizontal well with 5 1/2" 20# casing. The initial 17 stages were completed with the first BHA, at which time the tools were pulled out of the hole. Upon inspection, the packer was replaced and the remaining 23 stages were completed. Each stage was completed in an average of 4 hours utilizing two ZIPP™ System BHAs.

ONE COMPANY ONE SOLUTION

thrutubing.com

