


ZIPP™ System

57 Stages Completed with 1 BHA



HIGHLIGHTS

- Single Trip Perf-and-Frac
- Accurate Frac Placement
- No Additional Clean Out Run
- Durable Design

DETAILS

Location	Payne County, Oklahoma
Formation	Mississippi Lime
Well Orientation	Horizontal
Conveyance	2" Coiled Tubing
Casing Size	5 1/2" 17#
Operation Depth	11,222 Ft
Number of Stages	57
Tools Used	ZIPP™ System

RESULTS

The customer planned to perforate 57 stages in a horizontal well with 5 1/2" 17# casing. Per the customer's request, after the initial 40 stages the BHA was pulled to surface to evaluate the condition of the tools.

VALUE TO CLIENT

All the tools were in good condition and ran back in to complete the remaining 17 stages. All 57 stages were perforated and fraced in 5 days utilizing a single ZIPP™ System BHA.

ONE COMPANY ONE SOLUTION

thrutubing.com

